AllTerrain

Bid ID #: 11619

Helping you & your landscaping Shine

Prepared for:

Fossil Creek Condominiums Hammersmith Property Management 5620 Fossil Creek Pkwy
Fort Collins, CO 80525

(970)690-5116

pamela.sachs219@gmail.com

Created by:

Derrick Bleeker derrickbleeker@atpslandscaping.com







All Terrain

970-304-1183 atpslandscaping.com 5312 W. 9th St. Dr., Suite 120, Greeley, CO. 80634

About All Terrain Landscaping



Our mission is to help you look great.

All Terrain Landscaping began with a simple sprinkler job for a family friend. After earning multiple degrees, we launched the company, focusing on hand-dug ponds and sprinklers. Our first company vehicle was an '84 Mustang. The business grew quickly, and soon we were full-time landscapers. With a strong work ethic and a dedicated team, we became the largest lawn service and snow removal company in Greeley, eventually expanding into Fort Collins, Boulder, and beyond.

View Our Work



Project Details

Demo

Demo existing junipers throughout the property.

Grading and soil amendment for juniper removed areas

Equipment

MT100

Mini-Ex

Skid

Plants

- Installation of 40 5 gallon shrubs to be only native to Colorado
- Installation of 80 1 gallon perennials to be only native to Colorado

Rock

- Installation of 20.50 tons of 1-1/2" local river rock to replace areas where junipers are removed.
- Installation of 1800 square feet of landscape fabric to replace areas where junipers are removed.

Irrigation

All irrigation will be done on a time and material basis with a do not exceed of \$2,500

-Juniper removal will be done using various equipment due to root depth potentially running underneath sidewalks. All Terrain will dig out the junipers from all areas, amend the soil, establish positive drainage, install new fabric to removed areas, and install rock to the same areas. 12 Colorado native plants will be installed around each building to establish a healthy native environment to surrounding insects and species.

-Maintenance over the first year of the plants will consist of no pruning, increased water from the drip line for the first 3 weeks for establishment then standard watering expectations dependent upon the season.

6" NYOPLAST DRAIN PIPE, CONNECT TO DOWNSPOUT INFILL OPENING W. OUTDOOR KITCHEN