

All Terrain LANDSCAPING

Bid ID #: 16420

Helping you &
your landscaping *Shine*

Prepared for:

Mike Schmidke

13946 County Road 72

Greeley, CO 80634

(970)373-7749

Schmidkem@gmail.com

Created by:

Kaylor Werner

kaylorwerner@atpslandscaping.com



All Terrain
LANDSCAPING

970-304-1183 atpslandscaping.com
5312 W. 9th St. Dr., Suite 120, Greeley, CO. 80634

About All Terrain Landscaping

Our mission is to help you look great.

All Terrain Landscaping began with a simple sprinkler job for a family friend. After earning multiple degrees, we launched the company, focusing on hand-dug ponds and sprinklers. Our first company vehicle was an '84 Mustang. The business grew quickly, and soon we were full-time landscapers. With a strong work ethic and a dedicated team, we became the largest lawn service and snow removal company in Greeley, eventually expanding into Fort Collins, Boulder, and beyond.

View Our Work



Project Details

Planting Bed

- Installation of 43.5 tons of 1-1/2" white river rock
- Installation of 4,272 square feet of landscape fabric
- Installation of 8 tons of 2"-4" grey cobble
- Installation of 400 linear feet of metal roll top edging
- Installation of 3 - 15 gallon trees
- Installation of 9 - 5 gallon shrubs
- Installation of 6 - 5 gallon evergreen shrubs
- Installation of 12 - 1 gallon perennials

Fence

- Installation of 61 linear feet of vinyl 3 rail fence to match existing

Berm

Installation of Timber Wall to include:

- Installation of 1 ton of road base for base materials
- Installation of 1 ton of sand for base materials
- Installation of 23 6" by 6" by 8' long timbers for a 24 LF by 2.5-foot-tall wall
- Installation of 4 tons of 1-1/2" local river rock behind wall for drainage
- Installation of 14 yards of topsoil for berm
- Installation of 267 square feet of landscape fabric
- Installation of 3.5 tons of 1-1/2" white river rock
- Installation of 2.5 tons of Colorado buff boulders
- Installation of 3 - 5 gallon evergreen shrubs
- Installation of 31 - 1 gallon perennials

Irrigation

- Installation of drip irrigation to all new plants (tying onto existing drip system)

Wall

- Installation of 186 LF double sided veneer wall by 6 foot tall to include 1,116 CMU blocks, cap, and footer